



Risktopics

2-7.010 February 2010

When to initiate a roof snow removal plan

Removing snow from a roof is a challenging task. It is important to develop a safe and reliable practice for manually or automatically monitoring your roofs so action can be implemented quickly and effectively when needed.

Determine roof snow load design specifications

Structural drawings of the building should contain roof snow load specifications. A separate document detailing the design snow load calculations may also be available. If documentation for the building is not available, the services of a structural engineer should be retained to develop the snow load carrying capacity of the roof.

The design snow load will not be the same for all roofs at a site, and it may even change for various sections of an individual roof. Areas where a roof is exposed to drifting snow should possess higher design snow loads. Drifting snow can be caused by features such as:

- Walls of attached or even nearby taller buildings
- Higher nearby terrain
- Parapet walls
- Rooftop equipment

Determine actual roof snow load

A method that is accurate and avoids the safety issues associated with a person being on the roof is an approach proposed by the National Weather Service. This alternative involves collecting a core sample of the roof snow from any accessible point. This may be near a roof access door, hatch, window, fixed ladder, or other safe means of approaching the roof area. See Annex A for guidance on this recommended approach to estimating roof snow loads.

(Note: A frequently mentioned approach to determining the actual roof snow load is to collect and weigh all snow from a one square-foot area of the roof. This approach often involves a person going onto the roof to remove a heavy sample of snow to determine if the roof is safe. The obvious concern is the unknown exposure to the person collecting the sample.)

Consider other roof load factors

The design load for a roof will be a combination of the dead load (weight of the building materials and fixed equipment), live load (loads due to workers, tools, and equipment on the roof), wind loads, and snow loads. All of these loads, except the snow load, will be present year round.

Changes to roof loads during warm weather can lead to a surprise during a future cold weather snow event. Any change that increases the dead load will reduce the available snow load capacity.

Dead loads can increase by recovering a roof without removing the old roof cover. Likewise, dead loads can be increased by adding new fixed equipment on a roof or suspending new fixed equipment inside from a roof.

Changes can also occur that affect the amount of snow that develops on a roof. The addition of an attached or nearby building with a taller roof could lead to uncompensated increases in snow loads due to drifting on the lower existing roof. This addition of a taller building should include a re-evaluation of the snow load capacity of the existing building.

The change management plan for roofs should include the review by a structural engineer to guide needed structural upgrades. Without careful management of change, when snow arrives, the available snow load capacity may not be adequate to accommodate the anticipated snow event.

Decide on course of action

A variety of audible and visual signs may be present that indicate a safe roof snow load has been exceeded. If any indicators are present, assume the roof is unsafe and subject to failure. Immediately evacuate the building. Secure the services of a structural engineer to evaluate the integrity of the building before allowing personnel on or under the roof. These visual and audible indicators include:

- Building steel that is visually deformed
- Wood structural members that are cracked or split
- Sprinklers pushed down below ceiling tiles
- Doors that pop open or no longer operate correctly
- Utility pipes or conduits that are bowed out of normal position
- Structural noises including creaking, cracking, or popping sounds

The activity of removing snow from a roof is an arduous task. To handle the task safely requires reasonable work conditions and careful attention to safety. It is important to understand that snow removal is not considered safe and is not recommended during a snow storm.

Once a snowstorm is over and the building is not showing adverse visual or audible indications that a safe snow load has been exceeded, it is time to evaluate the need to take action. Is there a need to implement a roof snow removal plan?

Deciding to initiate a roof snow removal plan requires careful consideration. There is a need to compare the "roof design snow load" to the "actual roof snow load". If the actual snow load exceeds the design snow load, assume the roof is unsafe and subject to failure. See Annex A for guidance on a recommended approach to estimating roof snow loads. Immediately evacuate the building. Secure the services of a structural engineer to evaluate the integrity of the building before allowing personnel on or under the roof.

If there are no adverse visual and audible indicators and the estimated snow load does not exceed the design snow load, evaluate if there is a need to remove snow from the roof.

First, when it is safe to access the roof following a snowstorm, clear roof top drain inlets and outlets. Clear drains will help remove water from melting snow. Clogged drains can lead to severe ice accumulation. This can contribute to roof failures during a later snow or rain event.

Second, if the estimated roof snow load is approaching the roof design snow load, it is key to take proactive steps to safeguard critical assets and operations through snow removal.

Third, roof areas that accumulate drifting snow may warrant action to remove snow in the drift exposed areas. The deeper drifts will take more time to melt and drain away. This increases the likelihood that another snow or rain event can add to the actual roof snow load in these drift exposed areas.

Finally, even if the actual snow load is well below the design snow load, action may be needed if weather forecasts include snow or rain before the accumulated snow has time to melt and drain from the roof. In these cases, prompt action is needed. Keep in mind that snow will absorb rain like a sponge, preventing water runoff and significantly adding to the actual roof snow load.

Unless there are personnel on staff with experience to safely remove snow from a roof, secure the services of a qualified contractor to handle this task. Review detailed safety rule and regulations with all contractors and secure contractor signatures indicating they have received this training. Have contractors provide Certificates of Insurance verifying adequate levels of insurance for both Workers' Compensation and General Liability. Verify coverage is provided for property damage or bodily injuries caused by contractor's employees or their operations.

Plan and prepare for next winter

Being in a position to act effectively and efficiently requires advance planning. A formal roof snow removal "safe work plan" is an essential product of the advance planning. Incorporate OSHA fall protection guidelines in the safe work plan.

Retain a qualified contractor to implement the roof snow removal "safe work plan". This is a job for those with experience working safely at significant elevations above ground.

Confirm:

- The contractor is fully aware of all safety expectations.
- The contractor has provided Certificates of Insurance verifying adequate levels of insurance for both Workers' Compensation and General Liability. Verify coverage is provided for property damage or bodily injuries caused by contractor's employees or their operations.

Safely removing snow from a roof is an expensive undertaking. Therefore, if you will be periodically faced with making a decision to clear snow from a roof, it may be cost effective to consider a roof deflection monitoring system that can alert you when action is needed. Examples of companies* that can provide roof deflection monitoring systems include Safe Roof Systems <http://www.saferoofsystems.com> and Sensing Systems Corporation <http://www.sensing-systems.com/>. It is essential to evaluate available systems against the criteria of your particular situation.

There are several conditions that can increase the need for clearing snow from a roof. They include:

- Buildings housing high value equipment or stock where there is little desire to take chances with these high values.
- Buildings exposed to drifting snow due to roof height changes, parapets, or roof top equipment.
- Buildings designed to the 1993 or earlier edition of ASCE 7 "Minimum Design Loads for Buildings and Other Structures" which are designed to a lower roof snow load requirement than today.

For these situations, consider the cost-benefit case for a roof deflection monitoring system. These monitoring systems can provide clear criteria for when it is time to act. Avoiding one unnecessary snow removal effort may pay for the roof deflection monitoring system.

Conclusion

For further guidance or to discuss questions, contact your Zurich account team.

Annex A – One approach to estimating roof snow loads**

This recommended approach to estimating the roof snow load is intended to be applied without personnel going onto the roof. This alternative involves collecting a core sample of the roof snow from any accessible point. This may be near a roof access door, hatch, window, fixed ladder, or other safe means of approaching the roof area.

The core sample can be collected using a pipe of any diameter. An interesting element of the approach is that the pipe diameter does not impact the calculations. To keep the weight of the sample as light as possible, select the smallest diameter pipe available that will effectively collect the core sample.

To collect the snow core sample, use a capped section of clear plastic pipe having a length that exceeds the snow depth. Stick the pipe vertically down into the snow, and collect a full depth sample. When taking the sample, note the depth of the snow at the sample location. This can be accomplished by marking the sampling pipe.

Take the collected sample into a heated area and allow the snow to melt inside the pipe. Once the snow has melted, measure the height of water in the pipe. Using the following formulas, calculate the "estimate roof snow load" and the "estimated snow density" at the sample location.

(1) $P = 5.2 H$, where:

$P =$ Estimated roof snow load in pounds per square foot
 $H =$ Height of water in the pipe in inches

(2) $D = 12 P/S$, where:

$D =$ Estimated roof snow density in pounds per cubic foot
 $P =$ Estimated roof snow load in pounds per square foot
 $S =$ Measured snow depth at the roof sample point

To estimate the roof snow load at another location on the roof, there is a need to identify the depth of snow at that location. This can be accomplished by using the heights of known rooftop features such as equipment, parapets, and penthouses. Pre-marking walls and equipment with elevations or measuring sticks can also facilitate identifying snow depths. The overall objective is to visually identify the snow depths without actually going onto the roof.

Once a snow depth is identified at another location, the roof snow load at that location can be estimated using the following formula:

(3) $P = D S/12$, where:

$P =$ Estimated roof snow load in pounds per square foot
 $D =$ Estimated roof snow density in pounds per cubic foot
 $S =$ Estimated snow depth at the desired point on the roof

As a caution, any ice present under the measured snow layer may go unaccounted if care is not taken to include the ice layer if present. Each inch of ice represents an added roof load of 4.8 psf.

**Neither of these companies is a subsidiary or affiliate of Zurich and use of their products and services are independent of, and not included within, the any Zurich policy or any other Zurich product or service. Zurich expressly disclaims any and all damages and other costs that may arise related to the use of or reliance upon the products, services, representations or warranties made by or on behalf of these companies.*

***Zurich Services Corporation does not guarantee any particular outcome and there may be conditions on your premises or within your organization, which may not be apparent to us. You are in the best position to understand your business and your organization and to take steps to minimize risk, and we wish to assist you by providing the information and tools to help you assess your changing risk environment.*

Zurich Services Corporation

1400 American Lane, Schaumburg, Illinois 60196-1056
800 982 5964 www.zurichna.com

Zurich Services Corporation
Risk Engineering



ISO 9001:2008

Quality-Assured Solutions Provider

The information in this publication was compiled by Zurich Services Corporation from sources believed to be reliable. We do not guarantee the accuracy of this information or any results and further assume no liability in connection with this publication, including any information, methods or safety suggestions contained herein. Moreover, Zurich Services Corporation reminds you that this publication cannot be assumed to contain every acceptable safety and compliance procedure or that additional procedures might not be appropriate under the circumstances. The subject matter of this publication is not tied to any specific insurance product nor will adopting these procedures insure coverage under any insurance policy.

©2009 Zurich Services Corporation



Because change happenzSM